Soule Homestead Step 2 application submitted by Nov. 1, 2013

CPA Budget, Funding, Timeline

Total project budget: \$57,171

Note: All carpentry labor is estimated at \$30 / hr (\$240 / day per man)

Estimate Details House:

\$4,000 Chimney labor: Re-point and reflash 2 red brick chimneys above 2nd floor roof.

(Mason & Helper: 8 days @ \$500 / Day 8 X 500 = 4,000)

\$200 Materials \$200

\$11,200 Roofing labor & material Strip / dispose and replace 2800 square feet of asphalt roofing.

(Material and labor (including insurance) \$400 / sq =\$11,200)

33,360 Trim & gutter work labor (2 Carpenters 7 days = $14 \times 240 = 33,360$)

\$700 Material Materials \$700 Note: for wood gutter add \$2,500

\$2,400 Window labor 34 windows total (20 need some work)

\$100 Material (Average 4 hours / window @ \$30 hr = \$120 x 20 =\$2,400)

\$720 Shutter labor Labor to remove and replace 8 sets of shutters 3 hr / set = 24 hrs x \$30 = \$720

\$2,800 Material 8 sets @ \$350 set composite or wood = \$2,800

\$2,400 Siding labor Strip and re-side north walls 800 square feet pre stained white cedar extras

(2 carpenters 5 days = 10 X 240 = \$2,400)

\$3,600 Material Material 8 sq shingles x \$430 = 3,440 + nails and paper

\$1,920 Woodshed labor Replace a section of sill & rebuild small doors

\$300 Material (2 carpenters 4 days = 8 X 240 = \$1920)

\$33,700 Total

Estimate Details Barn:

\$4,800 Trim labor Repair and / or replace exterior trim where needed

\$1,000 Material (2 carpenters 10 days = 20 X 240 = \$4,800)

\$4,800 Siding labor Strip / dispose and re-side north walls 800 sq feet with unstained white cedar extras

(2 carpenters 10 days @ 480 / day = \$4,800)

\$2,400 Material 900 square feet white cedar extras @ \$200 / sq (\$1,800) + large vent, nails and paper

\$2,160 Window labor Replace 18 windows (2 hrs / unit x \$30 = 60 X 18 =\$1,080)

Repair & reglaze 12, 6 over 6 sash 3 hours each $(36 \times 30 = \$1080)$

\$6,000 Material 20 windows @ \$300 / unit =\$6,000

\$21,160 Total

\$33,700 house \$21,160 barn \$54.860 sub total

Non roofing labor \$26,560 \$2,311 Workmen's Comp Insurance 8.7% of \$26,560

\$57,171 Total project estimated cost

Administrative costs to be absorbed by Soule Homestead

Timeline

Work will be started as soon as funding becomes available and will be continued until completed.